

sales@excelmodular.co.uk

#### **Imposed Loads**

Floor - 3.0kn/m2 Roof - 0.7kn/m2

## **Design Wind Speed**

Walls - 0.41kn/m2 (Wind at 46m/sec)

### Fire Resistance Rating

Surface spread of flame: Class 'O' to walls and ceilings. Integrity: 30 minutes structural stability protection.

## Floor Structure - 'U' Value = 0.52w/m2 k

#### Joists

150 x 50mm GS graded timber floor joists at 406mm centres nailed to 150 x 50mm timber side plate.

#### Floor Deck

18mm flooring grade chipboard glued and nailed to floor joists.

### Insulation

Eco Bright or SFTV Multi Foil Insulation

# **Floor Covering**

2.0mm thick pure sheet vinyl with heat welded seams bonded onto chipboard deck.

## External Walls - 'U' Value = 0.58w/m2k

## Timber Framing

63 x 38mm CLS top and bottom rails with 63 x 38mm CLS vertical studding at 400mm centres with horizontal cross mid rails.

### Cladding

9.5mm WBP plywood glued and nailed to studding timber to form a stressed skin construction with Plastisol steel external finish c/w a balancer sheet on the inside face of the plywood for structural integrity.

### Insulation

60mm fibreglass insulation quilt fitted between vertical timber studding.

## **Internal Lining**

12.7mm white vinyl faced plasterboard fixed onto timber studding. Board joists finished with two part cream PVC 'H' section. All skirting and cornice are 45 x 9mm white plastic.

## Roof Structure - 'U' Value = 0.56 w/m2 k

#### **Roof Joist**

122 x 34mm TR26 roof joists at 406mm centres nailed to 122 x 34mm timber side plate

### **Internal Ceiling Lining**

12.7mm white vinyl faced plasterboard fixed onto timber roof joists, board joints finished with one part white PVC

### **Roof Deck & Covering**

11mm OSB is nailed to the roof joists weatherproofed with FATRA twin layer eco blanket manufactured to BS5750 giving a 'AA' fire rated finish.

#### Insulation

60mm fibreglass insulation quilt is laid between the roof joists directly above the ceiling.

#### **Roof Ventilation**

Cross ventilation above the insulation quilt via UPVC Plastic Roof vents at each end of roof, thus preventing the possibility of interstitial roof condensation.

### **Rainwater Discharge**

Rainwater is discharged directly from the roof via PVC square fall pipes to ground level.

#### **Fascia Details**

Plywood fascia is built onto the ends of the timber roof joists and nailed in place, then covered with Plastisol.

# Windows - "U" Value = 2.00w/m2/k

900 x 1000 uPVC double glazed white, fully opening vents glazed in pilkington 'k' clear glass with neoprene glazing gaskets, trickle vents and opening restrictors.

#### **External Doors**

UPVC doors fitted as standard (or Kirncroft steel composite insulated doors with 10 point locking system)

## **Electrical Installation**

An 18<sup>th</sup> Edition single phase consumer unit complete with RCD & MCB's is fitted with an external inlet box. Your Jackleg cabin will arrive direct complete with lighting, heating & power fittings. All units are pre-tested in the factory and come with Electrical Certification

# **Structural Design**

The structure is designed and constructed in accordance with the following standards and technical reference:

Building Regulations for England & Wales

BS5268 Pt2 2002 - Structural use of Timber

BS6399 Pt1 1996 – Design loading for Buildings. Dead & Imposed Loads

BS6399 Pt3 1988 – Design loading for Buildings. Imposed Roof Loads

BS6399 Pt2 1997 – Wind loads on Buildings.

BS5268 Section 6.1 1996 & 6.2 2001 – Structural use of Timber in Timber Framed Walls

BS5268 Pt3 1998 – Structural use of Timber. Trussed Rafter Roof

BS5950 Pt1 2000 – Structural use of Steel. Hot Rolled BS5950 Pt5 1998 – Structural use of Steel. Cold Formed Sections

Timber Designers Manual ~ E.C. Ongleton and J.A. Baird

Due to our company's policy for improvements, we reserve the right to change and/or amend the specification without prior notice.